

**TENDER FOR
LAYING INTERLOCK PAVING BLOCK AT
COIR COMPOSITE BOARD FACTORY,
KANICHUKULANGARA**

Tender No: FMIL/PROJ/CCBF/ILW- dated 28.01.2025

Foam Mattings (India) Ltd invites tenders from experienced civil contractors for the Laying of interlock paver blocks at plant building of FOMIL Coir Composite Board Factory, Kanichukulangara, Interested parties can participate in the tenders. Tender should be submitted in sealed cover superscribed with **tenders for the Laying of interlock paver blocks at coir composite board factory** addressed to:

**Managing Director,
Foam Mattings (India) Ltd
Post Box No. 4619, Beach Road, Alappuzha, Kerala, 688012**

Tender should include quoted rate signed and sealed by the contractor as per the technical specification.

GST should be mentioned separately.

1. SCOPE OF WORK

The scope of work is to lay interlock paving block inside the plant building at coir composite board factory, Kanichukulangara as per the specifications along with the tender.

2. TENDER DATES

1	Date of publishing of tender	28.01.2025
2.	Last date of submission of tender	04.02.2025 (5:00 PM)
3.	Opening of tender	05.02.2024 (11:00 AM)

3. TENDER FEE: -

Cost of tender document **Rs 1062.00 (Rupees one thousand and sixty two only)** (inclusive of GST 18%) should be paid at FOMIL cash counter and the receipt of the same should be placed along with the tender or the bidder can pay it as Demand Draft in favour of “Managing Director, Foam Mattings India Ltd”, payable at Alappuzha, in such cases the DD should be submitted along with the tender.

Tender fee is nonrefundable in any case.

4. Earnest Money Deposit: -

An EMD amount of **Rs. 4,500.00** (Rupees four thousand five hundred only) should be paid by the bidder. The EMD shall be paid as Demand Draft in favour of “Managing Director, Foam Mattings India Ltd”, payable at Alappuzha. OR the EMD amount can be paid at FOMIL cash counter and receipt of the same shall be placed along with the tender. In the case of bidders whose bids are not considered for placing order, the Earnest Money Deposit (EMD) will be refunded without any interest within 30 days from the date of issue of work order to the successful bidder.

The EMD of the successful tenderer will be considered as the security deposit, and which will be released only after the successful completion of work.

If the successful tenderer disagree to execute the work/fails to complete the work within the specified period, whose EMD will be forfeited.

All registered MSMEs in the state of kerala and having Udyog Aadhar registration or registration from any other bodies specified by the Ministry of Micro, small and Medium Enterprises will be exempted from the payment of Tender cost and EMD. No firms outside kerala are exempted from the payment of EMD and Tender cost.

5. PRICE:

- a. The bidder should submit rate for the interlock paving brick work as specified in the tender document.
- b. No additional charges will be given other than the quoted amount.
- c. Applicable GST should be mentioned in the Price Bid.
- d. The comparison of the rates offered shall be on the basis of the total rates offered inclusive of all taxes.
- e. The price quoted should be valid for a period of 12 months from the date of opening of tender.

The quoted price shall be fixed and firm and escalation on any account shall not be acceptable.

6. PAYMENT TERMS:

1. No advance payment will be released for the work.
2. Payments will be released against the submission of bills submitted against the completion of works.
3. Necessary TDS will be deducted from the bill amount.
4. Even though the quantity is mentioned in the schedule of works. The final bill amount will be finalized based on the actual measurement of work done at the site.

7. DETAILED SCOPE OF WORK:

Scope of work is to demolish the existing damaged floor of the plant building at coir composite board factory and to make the floor level and even for laying the interlock block. Lay the interlock block as per the specification in the tender document. Salient terms and conditions of the works are noted below:

1. The works should be done strictly as per the specifications of every work.
2. The work should be supervised by an experienced person.
3. Materials, labour and necessary equipments for the work shall be arranged by the contractor.
4. It is the responsibility of the contractor to mobilize the materials required for the work. Loading unloading stacking of materials are under the scope of the contractor.

Details of the works are noted below:-

SI No	Item	Unit	Quantity
1	Demolishing the existing floor up to an approximate depth of 1 or 2 inch (make the surface even level in all areas) removing the demolishing waste from the plant and dumping it outside the plant building. Cleaning and leveling the floor and making it ready for laying interlock paving bricks.	Ls	1
2	Providing and laying 80 mm thick interlocking paver block of with strong vibratory compaction and of approved size and design/shape laid in required colour and pattern over and including 50mm thick compacted bed of baby metal, filling the joints with coarse sand etc., all complete as directed by the Engineer-in-charge. Necessary skirting should be provided using PCC throughout the edge of the interlock paving blocks for arresting the dislocation of tiles.	Sq Ft.	4236

1. The quantity mentioned are tentative and it can increase or decrease as per the requirement of company at the time of work. Even though final bill will be calculated as per the actual measurement of the work done.
2. The demolishing work is in lumpsum, and the contractor should visit the site and confirm the area and quantity of the demolishing/cleaning works before submitting the rates.

8. GUARANTEE OF THE WORK

The contractor should guarantee the work for a period of 12 months from the date of completion of the works. Any damages happens to the works due to the poor quality of the work shall be rectified by the contractor without any additional cost.

9. PERIOD OF COMPLETION OF THE WORKS

All the works related mentioned in the tender document shall be completed within the 10 days from the date of acceptance of work order.

10. GENERAL CONDITION:

1. Foam Mattings (India) Ltd reserves the right to call for any further information. Any information furnished by the agency found to be incorrect at any stage would render their proposal being declared ineligible.
2. Foam Mattings (India) Ltd shall not be responsible for any postal delay. Incomplete applications may summarily lead to rejection.
3. All disputes are subject to Alappuzha jurisdiction.
4. Foam Mattings (India) Ltd shall have the right to reject any or all the proposal without assigning any reason.
5. Tenders received after the closing date and time mentioned above will be summarily rejected.
6. Tenders without meeting the eligibility criteria will not be considered.
7. The rates quoted should be inclusive of all labour charges, transportation charges, material cost etc. No additional amount will be released above the quoted rate.
8. Bidders are advised to visit the site and understand the sitecondition. Since land leveling is also included in the work, the bidder should take necessary measurements for calculating the rates.

Sd/-
Managing Director

Schedule of works

Laying of interlock paver block at coir composite board factory, kanichukulangara

Tender No: FMIL/PROJ/CCBF/ILW- dated 28.01.2025

SI No	Item	Unit	Quantity	Rate	Amount
1	Demolishing the existing floor up to an approximate depth of 1 or 2 inch (make the surface even level in all areas) removing the demolishing waste from the plant and dumping it outside the plant building. Cleaning and leveling the floor and making it ready for laying interlock paving bricks.	Ls	1		
2	Providing and laying 80 mm thick interlocking paver block of with strong vibratory compaction and of approved size and design/shape laid in required colour and pattern over and including 50mm thick compacted bed of baby metal, filling the joints with coarse sand etc., all complete as directed by the Engineer-in-charge. Necessary skirting should be provided using PCC throughout the edge of the interlock paving blocks for arresting the dislocation of tiles.	Sq Ft.	4236		
	Total Taxable amount				
	GST				
	Total				

All the rates quoted as per the specifications and terms and conditions in the tender document.

Signature.....

Name & address of the contractor/firm

.....

.....

.....

.....

Date.....

Place.....